



**Alabama State Port Authority**  
**Addendum to R&P or Specification Booklet**

**Project Name** Water Truck Loading Station / McDuffie Pond Water Recycling Facility

**Project #** 10360

**Addendum #1**

**To:** Prospective Bidders

**Date:** 7/10/2017

Plans and specifications are hereby amended as follows:

Item	Description
1	Bidders will include a one (1) year warranty for parts, equipment and labor.
2	Reference sheets 10360-003 through 10360-005: Nozzles, Inlets, and all corresponding pipe shall consist of A53 Type S, Grade B Schedule 40 steel pipe. Flanges shall be compatible with the steel pipe and also the connecting HDPE pipe.
3	Reference Sheet 10360-003, Notes, Item 4: Change reference to Sherwin Williams Macropoxy 5000 to Sherwin Williams Macropoxy 646-100
4	Reference sheet 10360-006 – Interior Structure Subgrade Preparation detail The backfill aggregate is not required to be compaction tested.
5	Delete Item 8 from the bid summary sheet “Contractor Proposal” (duplicates Item 7)
6	The only carbon steel pipe to be used, besides that internal to the two tanks, on the suction and discharge of the Pond Water Supply Pump.
7	The Contractor is to use IPS size HDPE pipe and may substitute SDR 17 HDPE pipe for SDR 21 HDPE pipe.

Please indicate your receipt of this addendum by adding the addendum number in the appropriate place in your Requisition & Proposal or Specification Book.

**Project Manager:**

Thomas M. Alvarez  
 251-441-7534  
 talvarez@asdd.com