



Alabama State Port Authority
Addendum to R&P or Specification Booklet

Project Name Water Truck Loading Station / McDuffie Pond Water Recycling Facility

Project # 10360

Addendum #2

To: Prospective Bidders

Date: 7/11/2017

Plans and specifications are hereby amended as follows:

Item	Description
1	A quote from Jim House & Assoc. was included with the bid package in order to provide information on the strainer. The first page of which contained a quote for a Flyght pump and 7.5HP motor was inadvertently included. This pump is not part of the project and should be disregarded.
2	There are no electrical devices that are powered inside the dike area of the retention pond.
3	The specification for the for the truck station light fixture has Photocell and switch in Series so that light will not function without Switch being turned on.
4	The truck pump is provided with a 25 hp motor.
5	The water truck is equipped with both 12v. and 24 volt power systems.
6	The pump supplier is supplying the pump and motor only, the contractor will provide all controls, control panels, remote control boxes, float switches, pressure transmitters, etc. There is not a preferred supplier for this equipment
7	The equipment the new breaker will be installed in, in southeast ECC bldg. is a General Electric AV-Line Switchboard 65K AIC Rated.

Please indicate your receipt of this addendum by adding the addendum number in the appropriate place in your Requisition & Proposal or Specification Book.

Project Manager:

Thomas M. Alvarez
 251-441-7534
 talvarez@asdd.com