



Alabama State Port Authority
First Addendum

Project Name: *Pier 3 thru 6 West Fence Camera Conduit*
Location: **Mobile, AL**
Project # : 10915 **TASK # :** 1 **July 2021**

First Addendum

Pier 3 thru 6 West Fence Camera Conduit

August 2, 2021



Alabama State Port Authority
First Addendum

Project Name: *Pier 3 thru 6 West Fence Camera Conduit*

Location: **Mobile, AL**

Project # 10915 **TASK #** 1 **July 2021**

1. Replace specification 8 with the following:
Provide new stranded copper wire conductors suitable for this environment as follows:
 Two no. 4 and one no. 6 for lighting circuit
 Two no. 8 and one no. 10 for camera circuit
Provide grounding as required by NEC for this application
2. Pre-bid meeting is optional as stated in the bid advertisement. Strike specification 10.
3. Saw cut and remove concrete ditch as necessary to install and connect conduit at camera poles and substation
4. Install new Stainless steel conduit from substation box to existing 120v and 480v panels
5. Demo existing conduit and conductors as directed by Owner and leave on site for disposal by others. Conduit to be neatly stacked in lengths not to exceed 20 feet.