



Alabama State Port Authority
Addendum to R&P or Specification Booklet

Project Name Pinto Crane Rail Failure – 2017 Replacement

PROJECT 10355 **CN** 2425 **Addendum #** 1

To: Prospective Bidders **Date:** 6/30/17



This Addendum contains the following information and becomes a part of the Bid Package.

Item	Description
1	<p>Contractor’s Proposal, Item 5 is changed as follows:</p> <p>Install new rail system with owner furnished material. This is to include Installation of new anchor bolts to replace the ones removed, sole plates, rubber pads, rail, and rail clips. Install grout and torque all bolts as per manufacturer’s specification.</p> <p>New Contractor’s Proposal is attached.</p>

2	<p>Demolition and Construction Specification, II PROJECT SCOPE, 2.2 Replacement Procedure, Additional Work is changed as follows:</p> <p><u>Additional Work</u></p> <p>Apply rust inhibiting solvent to sole plate nuts and leveling rod exposed thread.</p> <p>Torque all bolts as per manufacturer’s specifications.</p> <p>Thermite weld all joints of new 171 lb. rail sections.</p> <p>Install asphalt to trench after all work is completed.</p> <p>Clean work area and remove all construction debris from the Pinto Facility</p>
---	--

Please indicate your receipt of this addendum by adding the addendum number in the appropriate place in your Requisition & Proposal or Specification Book.

Project Manager:

William V. Boulton, P.E.
 Project Manager

Date

Contractor's Proposal

The Contractor hereby agrees to provide and install specified materials and equipment, and to perform all work previously specified in this proposal, specification, and drawings, for the prices outlined in the following schedule. The quantities listed may be increased or decreased during project execution. In the event the quantities do change, the unit price shall apply according to scope of work. It is **MANDATORY** that the Supplier fills out this sheet with the required information and submits it with the proposal.

All work shall be performed in accordance with the project drawings and specifications.

Description	Est Qty.	UO M	Unit Price	Value
1. Project Mobilization/Demobilization.	Lump Sum	All	LS	\$
2. Port Access Credentials, Bond and Insurance.	Lump Sum	All	LS	\$
3. Removal and demolition work. Remove 560 ft. of existing rail system complete with rail, rail clips, rubber pads, sole plates, and damaged anchor bolts.	Lump Sum	All	LS	\$
4. Remove existing grout the full length of the removed rail system.	Lump Sum	All	LS	\$
5. Install new rail system with owner furnished material. This is to include installation of new anchor bolts to replace the ones removed, sole plates, rubber pads, rail, and rail clips. Install grout and torque all bolts as per manufacturer's specifications.	Lump Sum	All	LS	\$
6. Install asphalt fill in the area of new rail installation and complete any remaining miscellaneous items as required for completion of project. Clean up area and remove all construction related items from ASPA property.	Lump Sum	All	LS	\$
7. Clean up area and remove all construction related items from ASPA property	Lumps Sum	All	LS	\$
	TOTAL BID			\$