



Alabama State Port Authority
Addendum to R&P or Specification Booklet

Project Name McDuffie Terminal – Stormwater Containment Facility West Cell
 Excavation

Project No. 10943 **Task No.** 1 **Addendum No.** 1


To: Prospective Bidders **Date:** 7/21/21

The following items are clarifications to questions received during the Pre Bid Meeting.

Item	Description
1	<ol style="list-style-type: none"> 1. <i>Where can the water from the pond be pumped?</i> The water can be pumped to the adjacent pond located to the east. 2. <i>How do I keep the water from flowing back from the adjacent pond once pumped over?</i> The means and methods for this will be left up to the individual contractor. However, building an earthen cofferdam has proven successful in the past. Foreign material would be permitted in the pond for this purpose only. Inflatable pipe plugs have also had moderate success. 3. <i>Where can the vegetation from the pond be taken?</i> Vegetation should be stacked in a designated pile adjacent to the clean coal stockpile location. 4. <i>What is the depth to the bottom of the pond?</i> Based on previous pre and post-excavation surveys of the pond, the depth is estimated to be around 7 foot.
2	No truck loading will be allowed from the east road between the west and center stormwater cells due to heavy rains and saturated soil conditions. A revised project plan drawing is attached for further clarification noting this roadway.

Please indicate your receipt of this addendum by adding the addendum number in the appropriate place in your Requisition & Proposal or Specification Book.

Project Manager:



 Wesley Jackson, EI 7/21/21
 Project Manager Date

PIPE STRUCTURE
DO NOT DISTURB.

PIPING AND SHEETPILE STRUCTURE.
REMOVE COAL FROM AROUND BUT DO NOT DISTURB.

EX. LEVEE ROAD

PERIMETER LEVEE ROAD FOR
TRUCK AND EQUIPMENT STAGING

NO TRUCK LOADING PERMITTED
ON THIS ROAD

EXCAVATE ALL COAL FROM WITHIN
STORMWATER POND AND HAUL TO THE
DESIGNATED STOCKPILE AREA ON
DRAWING 10943-01.
APPROX. 35,000 CY TO BE REMOVED.

WEST CELL DISCHARGE PIPE.
PLUG PIPE BEFORE DEWATERING
AND EXCAVATION

PERIMETER LEVEE ROAD
FOR TRUCK AND
EQUIPMENT STAGING

EX. LEVEE ROAD



NOTES:
1. THIS DRAWING IS FOR INFORMATIONAL PURPOSES AND IS INTENDED TO PROVIDE A BASIS FOR BIDDING. EXCAVATION LIMITS WILL BE DETERMINED IN THE FIELD AND BASED ON A SURVEYED BOUNDARY. THE CONTRACTOR SHALL EXCAVATE DOWN TO THE SOIL-COAL INTERFACE. NO SOIL IS TO BE REMOVED. STOCKPILED COAL SHALL BE 100% COAL.
2. FOR BIDDING PURPOSES, NOTED VOLUME OF MATERIAL TO BE REMOVED IS APPROXIMATE. THE ACTUAL VOLUME OF MATERIAL WILL BE DETERMINED IN THE FIELD AND BASED ON SURVEYED QUANTITIES.

MCDUFFIE TERMINAL
STORMWATER CONTAINMENT SYSTEM
WEST CELL EXCAVATION - PLAN

REVISIONS	DESCRIPTION
DATE	



ALABAMA STATE
PORT AUTHORITY
MOBILE, ALABAMA



PROJECT NO.:
10943
TASK NO.:
01
SCALE:
NTS
DRAWING NO.:
10943-02_R1